G R. S. 59]

GENERAL AND REVENUE SECRETARIAT.

1906-07
(Miscellaneous)

File No. 215

Serial Nos. (See II)

Papers Filed.

*Month*_____

SUBJECT.

Repairs to the Sri Markandeswara Swamy Temple at Kandya in the Chikmagalore Taluk.

PREVIOUS REFERENCES.	LATER REFERENCES.
	Mg 89-27-1-21

ate of the probable cost of repairing the Sree Sree Kandeyaswami temple at Khandya — Chickmagalur Taluk.

No	Details of work	No.	Dimensions			Contents	Total	
	Sree Man Kandeyaswami Temple							
1	Removing the existing concrete of the roof and forming roads where ever necessary							
	Varandha	1	12	13½	¼	41		
	Hall centre	1	27	27	¼	182		
	Garbhagudi	1	2½	20	¼	108		
	Total					331	Sft	331
2	Providing chunam concrete and laying two layers of flat tiles the lower layer with cement and the other with lime mortar & plastering over with nice mortar complete with proper slope.							
	Varandha	1	12	13½	.	162		
	Hall centre	1	27	27	.	729		
	Garbhagudi	1	12½	20	.	430		
	Total					1321	Sft	13·21
3	Plastering with mortar Gopuram & other places	Lump Sum					Rs	10/-
4	Fixing Kalasa New brass	Lump Sum					Rs	30/50
5	Teak wood battened heavy doors with iron work painting hooks & complete doors	2	2½	.	5	25	Sft	25
6	Repairing doors	Lump Sum					Rs	57
7	Cement pointing to the joints all over	Lump Sum					Sft	5·00
8	White washing Inside hall	4	27	.	8	864		
	Garbhagudi Prakara	1	74	.	8	592		
	Do inside	1	40	.	8	320		
	Ceiling of Do	1	10	.	10	100		
	Do Prakara	1	17	.	20	340		

	Ceiling of fallV Gopuram Varandha front							
	Varandha front			DO		472		
	Ceiling		1	13	14	172		
		Total Rs				743		37.43
9	Pointing the steps and resetting the fallen ones							
10	Removing trees and roots entering grubbed basement		2	7	3	42		0.42
								57
	Front entrance							
1	Fixing the old huge door with necessary repairs to front gateway and iron works &c							25 20
2	Removing the Concrete over roof		1	40	20	1/2	400	400
3	Refixing the displaced Top Slabs		1	40	20		800 Sft	800
4	Providing mortar concrete 6" and laying 2 layers of flat tiles the lower one with cement & the other with lime mortar		1	40	20	.	800 Sq	8.00
	And plastering with lime mortar &c complete							
5	Removing the earth heaped in front		2	18	11	4	1584	59
6	Removing roots of big trees &c roots entirely grubbed up			Lumpsum			Rs	20
	Compound wall							
1	Removing the fallen slabs and also those that are about to fall including earth between the two places		1	225	3	3	2025	2025
2	Constructing a compound wall of burnt brick in mortar stone in chunnam							
	Foundation of Compound wall		1	233	1½	2	699 Cft	699
	East Side wall		1	74	¾	5	278	
	Northern "		1	120	¾	5	450	
	Western "		1	40	¾	5	150	
	Pilasters at every 10 feet distance		24	1/3	1/8	5	152	1030
	Total						878 Cft	878
							1030	
3	Plastering with Chunnam mortar							
	Eastern wall		2	74	.	5	740	
	Northern "		2	120	.	5	1200	
	Western "		2	40	.	5	400	
	Total						2340 Sq	23.40
	add for Pilasters			Lumpsum			160	2502
	Drainage wherever necessary			Lumpsum			Rs	15

	burnt brick in mortar								
	including plastering	1	234	.	.	234	Rft	234	
5	cement pointing to the joints of slab	1	234	6	.	2808	Sft	28·08	
	Rear Gate								
	Removing the broken burnt stone beam over gate way and resetting loosened slabs	Lumpsum						Rs 5/-	
2	New burnt stone beames in place of broken ones	3	7	1 1/8	1	24	cft	24	
3	Repairing the door and refixing	Lumpsum						Rs 5/-	
4	Removing roots & trees in the Compound wall and resetting slabs wherever necessary	Lumpsum						Rs 50/-	
5	Fixing a Dhwaja stamba 20' including plat form and necessary Cermonies &c	1	20	1	1	20	cft	20/- Rs 25	
	Constructing a new Kitchen								
	Earth work excavation Front & rear walls	2	24 1/2	2	2	194			
	Side & cross walls	3	7 1/8	2	2	85			
	Steps	2	4 1/2	2	1/2	9			
	Total					288	cft	11	
2	Rough Stone in mortar								
	Filling foundation front & rear walls	2	24 1/4	2	2	194			
	Do Side and Cross walls	3	7 1/8	2	2	85			
	Steps foundation	2	4 1/2	2	1/2	9			
	Total					288	cft	288	
3	Rough Stone in mortar								
	Basement longitudinal walls	2	23 3/4	1 1/2	1 1/2	102			
	Side & cross walls	3	7 5/8	1 1/2	1 1/2	52			
	Steps basement	2	4 1/2	2	1/2	18			
	Total					168			
	Deduct for Slabs till Slabs of doors	3	5	1 1/2	1/2	11			
	Balance					157		157	
4	Burnt brick in mortar								
	Superstructure front & rear walls	2	23 3/8	1 1/8	8 5/8	454			
	Side and cross walls	3	8	1 1/8	9	243			
	Gables	3	9	1 1/8	9 ×3	45			
	Total					742			
	Deduct Doors	3	3	1 1/8	6	61			
	Windows	2	2 1/2	1 1/8	3	17			
	Total of doors	3	5	1 1/8	1/2	8			
	Sills & lintals of Windows	2×2	4 1/2	1 1/8	1/2	10			
	Total					96			

	Balance brought forward					646			
5	Teak wood wrought and put up								
	Ridge piece	1	26 3/4	3/4	6"	3.8			
	Rafters	2x12	8	2 1/4	4"	13.3			
	wall plates	2	26 3/8	3"	4"	4.4			
	Total					21.63	cft	22.0	
6	Roofing with Mangalore tiles over teak reepers & chunam borders &c Complete Front & rear	2	26	8 1/4		429	Sft	4.29	
7	Ridge tiles set in Mortar and cement pointing	1	26			26	Rft	26	
8	Teak wood battened door with iron clamps &c - Complete	3	3		6	54	Sft	54	
9	Teak wood battened windows with iron bars &c complete	2	2 1/2		3	15	Sft	15	
10	Chocolate painting Doors	2x3	3		6	108			
	Windows	2x2	2 1/2		3	30			
	Total					138	Sft	1.38	
11	Burnt stone Slabs using the Slabs removed from compound wall								
	Sill of doors	3	5	1 1/2	1/2	22 1/2			
	Lintels "	3	5	1 1/8	1/2	17			
	Sills & Lintels of windows	2x2	4 1/2	1 1/8	1/2	20			
	Steps	2	4 1/2	2 1/4	1/4	20			
	Total					80	Sft	80	
12	Chunam plastering								
	Outside abound	1	67 1/4		8 1/4	555			
	Gables	2	10 1/4		3	31			
	Inside abound room	2	36		9	648			
	Gables	4	8/2		3	48			
	Total					1282			
	Deduct Doors	3	3		6	54			
	Windows	2	2 1/2		3	15			
	Total					69			
	Balance					1213	Sft	12.13	
13	White and Colour washing over plastering						Sft	12.13	
14	Cement pointing basement abound	1	68 3/4		1 1/2	102	Sft	1.02	
15	Clearing site and filling basement trench once						No	57	
16	Flooring with Kadapa slabs on 3" Concrete cement pointing &c Complete								

	Room	1	10	.	8	80	
	Kitchen	1	8	.	8	64	
	Rear doors	2	3	.	1	6	
	Total					150	Sq/ft . 50
17	Putting up hearth	Lump Sum					Rs 5/-
18	Constructing a chimney for the escape of smoke and providing Hearth mortar and constructing drain	Lump Sum					Rs 15/-
19	Closing the well in the prakara with earth and covering with S Cab	Lump Sum					Rs 50/-
20	Clearing the Tree Jamandana Swami temple and stacking stones etc carefully in one place	Lump Sum					Rs 200/-
21	Amount to be realised by auctioning old slabs etc	Lump Sum					Rs 250.
22	Providing a shelter for the Anjaneya in front of the temple.	Lump sum					~~Rs~~ 100/-
3	providing Ashtabandha- nam to the Markandeya swami idol	— do —					~~Rs~~ 300/-

# of Estimate of probable cost for repairing the Sree Markandeswara Swamii temple at Khandya Bhickmagalur Taluk

Nº	Items of work	Per	Rate	contents	Cost
	Sree Markandeya Swamii temple				
1	Removing the Concrete of the roof	cft	. 1.	331	10 70
2	Providing Lime and Concrete and laying two layers of flat tiles the lower one with cement and the other with lime mortar plastering complete	Sqr	20	13·21	261,
3	Plastering with Mortar	Lump Sum			10
4	Fixing Kalasa new brass with necessary	do			~~30~~ 50
5	Teak wood batten heavy doors with iron work painting hooks & complete	Sft	2 1 12	25	~~44~~ 50
6	Repairing doors	Lump Sum			5
7	Cement pointing to the joints all over	Sqr	6	5·80	~~20~~ 30
8	White washing	Sqr	5	37·43	12
9	Pointing the steps & resetting the fallen ones	Sqr	4	0·42 ~~37·43~~	2
10	Removing trees & roots entirely grubbed up basement	Lump Sum			5
					445
	Total				~~399~~
	Front entrance				
1	Fixing the old huge door with the necessary repairs to front gate way	Lump Sum			~~20~~ 25
2	Removing the Concrete of the roof iron work and Painting	cft	. 1	400	12-24
3	Refixing the displaced top Slabs and forming Road and consolidating with	Sft	. 6	800	25
4	Providing mortar concrete 6" and laying 2 layers of flat tiles the lower one with cement & the other with lime mortar and plastering & complete	Sqr	20	8·00	160
5	Removing earth heaped in front	cyd	3	59	11
6	Removing roots of big trees & c (roots entirely grubbed up)	Lump Sum			20
	Total				215 ~~248~~
	Compound wall				
	Removing the fallen slabs & also those that are about to fall including earth between the two and utilizing the to close the well and filling in Sanitary pits.	cft	. 1 .	2025	127

2	Burnt brick in mortar in Compound wall	cft	4	6	~~878~~ 1030		
3	Plastering with 6 chunam mortar				~~23.46~~ 25.60		12 15
3A	draining where ever necessary						
4	Coping with burnt brick in mortar	Lin ft			234 ✓		
5	Cement pointing with neat and waterproofing	sft			28.08		~~42~~ 168

Total ~~7200~~ 1147

Rear Gate

1	Removing broken burnt stone beam and resetting loosened slabs	Lump Sum					5
2	New burnt stone slabs beams	cft	1/2	12	24		~~42~~ 48
3	Repairing the door and refixing dressing etc complete	Lump Sum					5 ✓
4	Removing roots & trees in the compound wall and resetting slabs wherever necessary	Lump Sum					5 ✓
5	Fixing a Dhwaja steam to be dressed	cft	2	12	20		~~35~~ 40
5A	Platform with Stone Total in Chunam with available Slabs etc	unp Sum			Rs		~~137~~ 28 ~~143~~ 178

Constructing a new Kitchen

1	Earth work excavation	cyd		2	6	11 ✓	2
2	Rough stone in mortar	cft		~~5~~ 4		288 ✓	~~72~~ 90
3	do do	cft		5/4		15.7 ✓	~~39~~ 49
4	Burnt brick in mortar	cft		4	6	646 ✓	182
5	Teak wood 1st class wrought & put up	cft		~~5~~ 6	8	~~29~~ 22	~~12~~ 132
6	Roofing with Mangalore tiles over teak keepers & chunam borders etc Complete	Sqr		~~32~~ 24		4.29	136 ~~103~~
7	Ridge tiles set in mortar and cement pointing	Rft			~~8~~ 10	26 ✓	~~13~~ 16
8	Teak wood battened door with iron clamps etc complete	Sft	2	12		57 ✓	95
9	Teak wood battened windows with iron bars etc complete 3/4" dia bars	Sft	~~2~~ 7	12		15 ✓	~~26~~ 30
10	Chocolate painting	Sqr	6/4			1.38 ✓	5 8
11	Burnt Stone Slabs using the slabs removed from the Compound	Sft		4		80 ✓	20
12	Chunam plastering	Sqr	5			12.13 ✓	61
13	White washing & color washing	Sqr		5/4		12.13 ✓	~~4~~ 5
14	Cement painting	Sqr	65			1.02 ✓	~~5~~ 6
15	Clearing Site & filling basement	Lump Sum					5
16	Flooring with Kadapa Slabs on 3" Concrete Cement pointing & complete	Sqr	~~40~~ 35			1.50 ✓	~~60~~ 53
17	Putting up hearth	Lump Sum					5 ✓
18	Constructing a chimney for free escape of smoke & providing pestle & mortar & Constructing drain	Lump Sum					15 ✓ ~~20~~

Closing the well in the Prakara forth
and Covering with Slabs Earth
Removing the Sree Jayardanaswamy
Temple and stacking the stones
Carefully in one place
22 Providing a shelter for the Anjaneya
Swamy in front of the temple
23 ~~Providing Ashtabandha~~ ~~Shama~~
~~Sree Prankaneya Swamy idol~~

Total

21 Deduct probable amount to be realized from auctioning old slabs &c

Balance

Add Contingencies at 5%

Grand total

33
210
I 50.
II 200
III 100
300
1362
(250)
1112
2616
131
2747

Total 3290 3590
Contingencies 165 180
3455 3770
3539
3820
4166

*These materials may be utilized for Sri Anjaneyaswamy temple.

Bangalore
19th June 19

Establishment charges 10½ %
Grand Total Rupees

C. Narasappaiah
Assistant Engineer
Mineral Department

add. 10½ % for establishment charges

2712
250

Providing ~~Ashtabandha~~

300

3012

C.N.
13/8/19.

Checked

Contingencies & estimate as corrected includes
4166
Establishment charges on 3820/-

ಜ್ಞಾಪನ

ಇತ್ತೀಚೆಗೆ ಸಾರ್ವಜನಿಕರಿಂದ ಕಂಡುಬಂದಿದೆ. ಮೇಲಿಂದ ಕೆಳಗೆ ಬರೆಯಲಾಗಿದೆ
ಮೇಲಿನ ಸಾಲಿನ ಕೆಳಗೆ ಮತ್ತೊಂದು ಸಾಲು ಬರೆಯಲಾಗಿದೆ. ಮೇಲಿನ
ಜ್ಞಾಪನದಲ್ಲಿ ಈ ಕೆಳಗಿನ ವಿಷಯಗಳನ್ನು ಪ್ರಕಟಿಸಲಾಗಿದೆ.

1 ಕೆಲಸವನ್ನು ಪೂರೈಸಲು ಗುತ್ತಿಗೆದಾರರಿಗೆ ನೀಡಿದ ಕಾಲಾವಧಿ 272 ದಿನಗಳು ದಿನಾಂಕ 17.7.15
ಗಾಯತ್ರಿ 215-06 ಪ್ರಕಾರ

2 ಪ್ರಾರಂಭವಾದ ದಿನಾಂಕ 12-5-1916 ಸೇರಿಲ್ಲ

3 ಪೂರ್ಣಗೊಳ್ಳಬೇಕಾದ ದಿನಾಂಕ 28.9.15 ಸೇರಿಲ್ಲ

4 ಕೆಲಸ ಪೂರ್ಣಗೊಂಡ ದಿನಾಂಕ 31.8.16 ಸೇರಿಲ್ಲ

5 ಕೆಲಸದ ವೆಚ್ಚ — 136
17

6 ಮೇಲ್ವಿಚಾರಣೆಯ ಅಧಿಕಾರಿಗಳು ಸಹಿ ಮಾಡಿಲ್ಲ

ಮೇಲಿನ ಎಲ್ಲಾ ವಿಷಯಗಳಲ್ಲಿ —

ಕಾರ್ಯನಿರ್ವಾಹಕ ಎಂಜಿನಿಯರ್

272
mug 21.5-06.

From

V. R. Thyagaraja Iyer Esqr. M.A.
Secretary to the Government
of His Highness the Maharaja of Mysr
Revenue Department.

To

K. Krishna Iyer Esqr.
Deputy Commissioner
Kadur district

Dy 27th July 1915.

Sir.

With reference to your letter no 40 dated the 19th July 1915 submitting an Estimate for Rs 5510 for the repairs of the Sri Markandeswaraswami temple at Khandya, I am directed to request information as to whether the temple has any devotees who are in a position to contribute towards the cost of the repairs and if so how far they would be willing to subscribe for the same.

I have &c

Sd/ G. Arunnundaswamy
For Secretary to Govt
Revenue Dept

Deputy Commissioner

ఆ. శ్రీ శంకరాపురం కాపుల కులపు అనుమతి

ఆ కాపులు 54 / 18.4.16 నాటి అర్జీ

కు. సం. 429/ఆ

ఈ కాపులకేమి అభ్యంతరం అందువా. ఈ దేశమున్నే నాళ్ళే ఇక్కడి నాయకులు ఉత్తరాది-తేలుగు ఉద్యమాలు ఉంటున్నాయి ఇక్కడి నాయకులూ తళుకు బెళుకు అనుకుంటున్నారో ఏమో కాని ఈ. సం. 272/ముద్ర 215-06 తారీఖు 27/7/15 నాటి ఉత్తరువులో ఉన్నట్లు ఎందరు వినతులను తీసుకున్నట్టే ఉన్నట్లు ఇక్కడ ఉన్నట్లు ఇక్కడ ఉన్నట్లు ఇక్కడ

100

Received
on 5-10-15

ಸಿ.ನಂ. 235.

ಅಜ್ಜಂಪುರ: ತಾ|| 29-2-15.

ಈ ಬಾಬ್ತಿನ ಅರ್ಜಿಯನ್ನು ಸಲ್ಲಿಸಿರುವುದಾಗಿ ಅರ್ಜಿದಾರರು ತಿಳಿಸಿರುವುದರಿಂದ ಅರ್ಜಿಯನ್ನು ಹಿಂತಿರುಗಿಸಲಾಗಿದೆ.

ತಹಸೀಲ್ದಾರ್.
ಅಜ್ಜಂಪುರ.

ಸ್ಟಾಂಪ್ ಪೇಪರ್ ಖರೀದಿ ಮಾಡಿದ ವಿವರ

ಕ್ರ.ಸಂ. 14997 ರೂ. 100/-

ಕ್ರ.ಸಂ. 1336 ರೂ. 20/-

ಒಟ್ಟು ರೂ. 120/-

ಸ್ಟಾಂಪ್ ಪೇಪರ್ ಖರೀದಿ ಮಾಡಿದವರು

ಸ್ಟಾಂಪ್ ಪೇಪರ್ ಖರೀದಿ ಮಾಡಿದ ದಿನಾಂಕ

ಸ್ಟಾಂಪ್ ಪೇಪರ್ ಖರೀದಿ ಮಾಡಿದ ಉದ್ದೇಶ

ಸ್ಟಾಂಪ್ ಪೇಪರ್ ಖರೀದಿ ಮಾಡಿದ ಹೆಸರು

ಸ್ಟಾಂಪ್ ಪೇಪರ್ ಖರೀದಿ ಮಾಡಿದ ಸಹಿ

4

తేదీ 31-3-13.

Rev.-Gen

14 0 c 13

15

5

REMINDER

ತಗಾದೆ.

ಶ್ರೀಯುತ ಜಿಲ್ಲಾ ಡೆಪ್ಯುಟಿ ಕಮ್ಮಿಷನರ್ ಸಾಹೇಬರವರು.

ಶಿವಮೊಗ್ಗ ತಾಲ್ಲೂಕು ಅಮಿಲಾರಿಗೆ ಹುಕುಂ.—

ಇರೇಬಿಯಲ್ಲಿ ವಿವರಿಸಿರುವ ಸಂಗತಿ ಕುರಿತು ಇಲ್ಲಿಂದ ಕೊಟ್ಟಿರುವ ನಂ 10-5-1916 ನೆ ಮಿ॥ ನೆ ನಂ॥ ಹುಕ್ಕುನಿಗೆ 3 ದಿವಸಗಳ ಒಳಗಾಗಿ ಜವಾಬ್ ಕೊಡಬೇಕು—ಅಥವಾ ಆಲಸ್ಯಕ್ಕೆ ಕಾರಣ ತಿಳಿಸ ಬೇಕು.

ಪಾಂಥಿಕವಲಂ ಕಡಿದಿಕ್ಕಿರಲ್ಲಿ ಮಣೆಯನ್ನಿ ನಡಗಿಳಿದ
ಸಾಲದಲ್ಲಿ ನಡೆದ ಅಕ್ರಮಗಳು

ಸಂಗತಿ

ತಾ॥ 9 ನೆ ಮಾಹೆ ಸೆಪ್ಟೆಂಬರ್ 1916 ನೆ ಇಸವಿ

ಜಿಲ್ಲಾ ಡೆಪ್ಯುಟಿ ಕಮ್ಮಿಷನರ್.

WD 01842—GPB—23,027—17 2-1

ಸ್ವೀಕರಿಸಿದ ದಿನಾಂಕ

6658
21.10.16
accts

ELECTION COMMISSIONER'S OFFICE,
KADUR DISTRICT

6

No. C 136
1.5.16.

427
12.5.16.

Copy of docket No. 248 dated 27th August 1914, from the Executive Engineer, Kadur Division, to the Deputy Commissioner, Kadur District.

Has the honor to return duly signed the Estimate for Rs. 5,510/- for Repairing the Markandeyaswamy Temple at --- Khandya, received with his No. 44 dated the 15th instant.

-------OOOOO------

" C O P Y "

Deputy Commissioner,
Kadur District.

C.M.K.

Abstract estimate of the probable cost of repairing the Sri -- Markandeswaraswami temple at Khandya, Chickmagalur Taluk.

No.	Items of work.	Per.	Rate.	Quantity.	Cost.
1.	Removing the existing concerete of the roof and levelling the compound and consolidation -- with sand.	Cft.	0-1-0	331	20/-
2.	Providing chunam concrete and laying 2 layers of flat tiles the lower one with concrete and the other with lime mortar with proper slopes plastering etc., complete.	Sqr.	20-0-0	13.21	261/-
3.	Plastering with mortar.	L.S.			10/-
4.	Fixing Kalasa with new brass with necessary ceremony.	L.S.			50/-
5.	Teak-wood battened heavy door with ~~xxxxxxxx~~ iron work chocolate painting hooks, etc., complete.	Sft.	2-0-0	25	50/-
6.	Repairing doors.	L-S.			5/-
7.	Cement pointing to the joints all over.	Sqr.	6-0-0	5.00	30/-
8.	White-washing.	Sqr.	0-5-0	37.43	12/-
9.	Pointing the steps and resetting the fallen ones.	Sqr.	4-0-0	0.42	2/-
10.	Removing trees and roots entirely grubbed up basement.	L.S.			5/-
	FRONT ENTRANCE.				
1.	Fixing the old huge door with necessary repairs to frong gate way iron work and painting.	L.S.			25/-
2.	Removing the concrete of the roof and forming road and consolidation with sand.	Cft.	0-1-0	400	24/-
3.	Refixing the displaced top slabs.	Sft.	0-0-6	800	25/-
4.	Providing mortar concrete 6" and laying 2 layers of flat tiles the lower one with cement and the other with lime mortar plastering, etc., complete giving proper slopes.	Sqr.	20-0-0	8.00	160/-
	COMPOUND WALL.				
1.	Removing the fallen slabs and also those that are about to fall including earth between the two and utilizing the e earth to close the well and filling insanitary pits.	Cft.	0-1-0	2025	127/-

	COMPOUND WALL.				
2.	Stone in chunam for foundation.	Cft.	0-5-0	669	209/-
3.	Burnt brick in mortar compound wall with pillasters.	Cft.	0-6-0	1030	386/-
4.	Plastering with chunam mortar.	Sqr.	5-0-0	25	125/-
5.	Drainage wherever necessary.	L.S.			15/-
6.	Coping with burnt brick in mortar.	Rft.	0-8-0	234	117/-
7.	Cement pointing to the slabs with neat joints and watering.	Sqr.	6-0-0	28.08	168/-
	REAR GATE.				
1.	Removing broken burnt stone beam and resetting loosened slabs.	L.S.			5/-
2.	New burnt stone beams dressing, etc., complete.	Cft.	2-0-0	24	48/-
3.	Repairing and refixing the door.	L.S.			5/-
4.	Removing roots and toors and trees in the compound wall and resetting slabs wherever necessary.	L.S.			50/-
5.	Fixing a Dwajasthamba.	Cft.	2-0-0	20	40/-
6.	Platform with dressed stone in chunam with availabls slabs and necessary puja, etc.,	L.S.			25/-
	CONSTRUCTING A NEW KITCHEN.				
1.	Earth work excavation.	Cyd.	0-2-6	11	2/-
2.	Rough stone in mortar.	Cft.	0-5-0	445	139/-
3.	Burnt brick in mortar.	Cft.	0-4-6	646	182/-
4.	Teak wood wrought and put up.	Cft.	6-0-0	22	132/-
5.	Roofing with First Class Mangalore tiles on teak reapers, chunam borders, etc., complete.	Sqr.	32-0-0	4.24	136/-
6.	Ridge tiles set in mortar and cement pointing.	Rft.	0-10-0	26	16/-
7.	Teak-wood battened doors with iron clamps, etc., complete.	Sft.	2-12-0	54	95/-
8.	Teak wood windows with iron bars, etc., complete $\frac{3}{4}$" diameter bars.	Sft.	2-0-0	15	30/-
9.	Chacolate painting.	Sqr.	6-0-0	1.38	8/-
10.	Burnt stone slabs using the slabs removed from the compound.	Sft.	0-4-0	80	20/-
11.	Chunam plastering.	Sqr.	5-0-0	12.13	61/-
12.	White washing and color washing.	Sqr.	0-6-0	12.13	6/-

	~~EXTERNAL WORK.~~				
13.	Cement pointing.	Sqr.	6-0-0	1.02	6/-
14.	Clearing site and filling basement.	L.S.			5/-
15.	Flooring with Kadapa slabs on 3" concrete cement pointing, etc., complete.	Sqr.	35-0-0	1.50	53/-
16.	Putting up a hearth.	L.S.			5/-
17.	Constructing a chimney for the escape of smoke and providing pestle and mortar and constructing drain.	L.S.			15/-
	MISCELLANEOUS.				
1.	Closing the well in the Prakara with earth and covering with slabs.	L.S.			50/-
2.	Clearing the Sri Janardanaswami temple and stacking the stones carefully in one place.	L.S.			200/-
3.	Providing a shelter for the Anjaneyaswami temple in front of the temple using the old slabs.	L.S.			100/-
4.	Providing Ashtabandana to Sri Markandeswaraswami temple.	L.S.			300/-

Total.....Rs.	3,590/-
Add contingencies at 5%.....Rs.	180/-
Establishment charges @ 10½%..Rs.	396/-
GRAND TOTAL.	4,166/-

"C o p y."

Secretary to Government,

Muzrai Department.

HRR-2.